

**PART - I : FINANCIAL BID**

Name of work: Tender for Re-surfacing of Road at IPR Bhat, Gandhinagar  
IPR TENDER Notice No : IPR/TN/CIVIL/1/2015 dated: 23.3.2015 (Two Bid System)

From  
NAME OF THE CONTRACTOR :  
Offer no & date:

Sr. No.	Description of Work	Unit	Total quantity	Rate (in Rs.)	Amount (in Rs.)
	<b>Note : 1)For more detailed description of any material or item contained in the BOQ, please refer Part-II technical bid. If the detailed specs for a particular item is not contained in the Part-II technical bid, the description given in the BOQ shall have to be referred. 2) All items mentioned in the tender shall be executed as per the instruction and direction of Engineer-in-charge.</b>				
1	Providing and laying 50 mm. thick consolidated carpet course by heating and mixing asphalt and aggregate with continuous batching hot mix plant, spreading the same by paver finisher machine using B.T. Chips (stone aggregates) 12 mm. to 20 mm. size and sand in required proportion as per required gradation and asphalt 60/70 or 80/100 at a rate of 4.00 to 4.50 % by weight of mix and applying tack coat at a rate of 0.50 kg/m <sup>2</sup> of bitumen emulsion on existing asphalt road surface including scraping, brooming, cleaning the surface using air compressor, transporting, spreading and consolidating with power roller of 8 to 10 ton so that the resulting surface is even, smooth and in perfect line and level to the satisfaction of Engineer-in-charge with all required tools, plant, machinery, labours, oil, kerosene, firewood etc. complete as directed.	Sqm	22000		0.00
2	Providing and laying 20 mm. thick consolidated seal coat over carpet by heating and mixing asphalt and aggregate with continuous batching hot mix plant, spreading the same by paver finisher machine using B.T. Chips (stone aggregates) 10 mm to 12 mm size and sand in required proportion as per required gradation and asphalt 60/70 or 80/100 at a rate of 4.50 % by weight of mix and flushing the sand at rate of 0.03 m <sup>3</sup> /10 m <sup>2</sup> laid over tack coat of paving bitumen S-90 of penetration 80/100 of approved quality at 0.25 Kg/Sqm of road surface including scraping, brooming, transporting, spreading and consolidating with power roller of 8 to 10 ton so that the resulting surface is even, smooth and in perfect line and level to the satisfaction of Engineer-in-charge with all required tools, plant, machinery, labours, oil, kerosene, firewood etc. complete as directed.	Sqm	22000		0.00

Sr. No.	Description of Work	Unit	Total quantity	Rate (in Rs.)	Amount (in Rs.)
3	Providing and laying dense graded bituminous macadam with continuous batching hot mix plant using crushed aggregate of specified grading, pre-mixed with bituminous binder at 4 to 4.5% by weight of the total mix and filler, transporting, laying with hydraulic paver finisher with sensor control to required grade, vibratory and tandem rollers to achieve the desired compaction as per Morth & H specification clause 507 complete in all respect including tack coat of paving bitumen S-90 of penetration 80/100 of approved quality at 0.50 Kg/Sqm of road surface including scraping, brooming, cleaning the surface using air compressor, transporting, spreading and consolidating with power roller of 8 to 10 ton so that the resulting surface is even, smooth and in perfect line and level to the satisfaction of Engineer-in-charge with all required tools, plant, machinery, labours, oil, kerosene, firewood etc. complete as directed for making the existing road levelling by repairing of pot holes, undulation and making of bumps etc.	Cum	50		0.00
4	Providing and applying 2.5 mm thick road marking strips (retro-reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. using APCOMARK" retroreflective thermoplastic road marking material from ASIAN PAINTS"	Sqm	75		0.00
<b>C</b>	<b>Total Amount for Road work (in Rs.)</b>				-
<b>D</b>	<b>Rebate in Rs. (If Any):</b>				-
<b>E</b>	<b>Total Amount for Road works after rebate (in Rs.)</b>				-
<b>F</b>	<b>Service Tax in %</b>				-
<b>G</b>	<b>Service Tax (in Rs.)</b>				-
<b>H</b>	<b>Total Amount for Road works including Service Tax (in Rs.)</b>				-

**1) If the rate cells left blank, it will be treated as "0" (ZERO)**

**2) Kindly enable the Macros if you receive the "Security Warning" message. (Click on options in "Security Warning" and select "Enable this content")**