INSTITUTE FOR PLASMA RESEARCH

NEAR INDIRA BRIDGE, BHAT, GANDHINAGAR -382 428 (INDIA)

PART - I : FINANCIAL BID

Name	of work: Tender for Civil works for false ceiling / in	terior	and reno	ovation	work a				
first f	loor offices (old Building) at Institute for Plasma Resea	rch (IP	R). Bhat	. Gandl	hinagar				
IPR TENDER Notice No: IPR/TN/CIVIL/08/2019 dated 8th January 2020 (Two Bid Sys From									
	E OF THE CONTRACTOR :								
Offer	no & date:	1	1	l					
Sr. No.	Description of Work	Unit	Total quantity	Rate (in Rs.)	Amount (in Rs.)				
	Note: 1)For more detailed description of any material or item contained								
	in the BOQ, please refer Part-II technical bid. If the detailed specs for a								
	particular item is not contained in the Part-II technical bid, the								
	description given in the BOQ shall have to be referred. 2) All items								
	mentioned in the tender shall be executed as per the instruction and								
	direction of Engineer-in-charge.								
	D 11 10 1 1 1 0 1 1 1 1 1 1 1 1 1 1 1 1								
1	Providing and fixing combination of Luxalon 75C & 150C unperforated								
	aluminum panel ceiling manufactured by M/s. Hunter Douglas India Pvt.								
	Ltd. of consisting of panel 75mm and 150mm wide x 15.50mm deep and of 0.50mm thick TCT (Total Coating Thickness) with bevel edge, panel								
	length up to 6m, coil coated on a continuous paint line, double baked and								
	roll formed from enameled corrosion resistance aluminum alloy HD 5050								
	for higher strength and good roll forming characteristics. The panels abet								
	each other with a narrow V groove. Panel colour shall be of metallic								
	finish of approved shade. Panel shall be clipped to a baked enameled								
	panel carrier of 32mm wide x 39mm deep and 0.95mm thick in standard								
	length of 5m made of doubled baked enameled aluminum alloy HD 5050								
	black in colour with cut outs to hold the panels in a module of 150mm at a								
	distance of 1.2m c/c. Panel carrier shall be suspended by means of GI								
	suspension rod 4mm diameter which is connected to GI hook fixed in		1200		0.00				
	ceiling and a galvanized suspension spring clip at a distance of 1.00m c/c								
	or to be fixed with required size SS screws / fastners and washer directly								
	with RCC structure. Luxalon 30B profile of size 30mm wide x 15mm deep with square edge of 0.35mm thick aluminum of approved colour or same								
	colour as of panels shall be used as edge angle / wall angle. Panel splices								
	made out of black enameled aluminum shall be used to join two panels.								
	Carrier splice made out of black enameled aluminum 0.95mm thick. All								
	the material including ceiling panel, carrier, wall angles, suepecsion								
	system etc should be of approved manufacturer's specifications "M/s.								
	Hunter Douglas India Pvt. Ltd."								
	PAINT FINISH: Aluminum panels shall be chromatised for maximum								
	bond between metal and paint, enameled twice under high temperature,								
	one side with a full primer and finish coat the other side (inner side) with								
2	Providing and laying 25mm thick Phenotherm with Kraft paper facing on								
	both sides with 32 Kg/sqm density (M/s Bakelite Hylum), between RCC	Oqiii	1200		0.00				
	slab and metallic false ceiling to be fixed necessary hardware, chemical								

Sr. No.	Description of Work	Unit	Total quantity	Rate (in Rs.)	Amount (in Rs.)
3	Removing and re-fixing of existing electrical fixtures – fan including disconnection and reconnection of the same in operation condition, necessary connecting wiring work if required, cutting of the ceiling, executing etacking as directed at a instructed and directed by engineer	Each	100		0.00
4	Removing and re-fixing of existing electrical fixtures – tube light including disconnection and reconnection of the same in operation condition, necessary connecting wiring work if required, cutting of the spiling according stacking as directed decrease instructed and directed by	Each	200		0.00
Α	Total Amount for Works (A) (in Rs.)				1
В	Rebate in Rs. (If Any):				
С	Total Amount for flase ceiling works after rebate (in Rs.) inc		-		

Note: This is an indivisible works contract. The rates quoted shall include all taxes including Goods and Service Tax (GST) at applicable rates and levies, duties, cess etc., payable under respective statues. Deductions as per statues will be effected from the bill and remitted to the Department concerned.

¹⁾ If the rate cells left blank, it will be treates as "0" (ZERO)

²⁾ Kindly enable the Macros if you receive the "Security Warning" message. (Click on options in "Security Warning" and select "Enable this content"